

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of the Work: Improvements to roads and drains at Balaji layout surroundings in ward no. 8, kodigehalli sub-division

Sl. No.	Quantity	Description	Unit	Rates	
				In Figures	In Words
1	180.00	1321 Hire charges of 100 KVA generator including operator, fuel, transportation and handling charges PWD SR 2013-14, P. L, I. 92 for pumping of stagnated water in existisng drain	Hour s	495.00	
2	1399.29	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	cum	75.60	
3	180.80	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications.- Rubble stone masonry in cement mortar	cum	993.60	
4	18.34	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. - RCC grade M20 and above	cum	954.72	
5	5978.07	Removing B.S Slab of Drain and stackin	sqm	58.32	
6	785.44	Construction of embankment with approved material deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of Table 300-2 complete as per specifications which includes watering charges and compaction	cum	166.32	
7	4184.64	Refixing stone slabs of drains and pointing in C.M (1:3)	sqm	75.60	
8	1793.43	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete - 10.0 cms thic	sqm	704.16	
9	243.94	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	Cum	4847.04	

Sl. No.	Quantity	Description	Unit	Rates	
				In Figures	In Words
10		Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications	Cum		
10A	126.56	With Available stones	cum	3585.60	
10B	34.15	With New stones	cum	4773.60	
11	714.27	Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications cement mortar 1:4	sqm	92.88	
12	62.86	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @ 0.56 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5287.68	
13	48.90	Providing and constructing precast concrete solid blocks with compressive strength not less than 3.5 N/sqmm with CM 1:4 masonry with solid concrete blocks of size 40x20x20 cm conforming to IS 2185 / 1965 in superstructure including cost of all materials, labour charges, scaffolding, curing complete as per specifications.	sqm	993.60	
14	1388.53	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	73.57	

ಕರಡು ಬೆಂದರ್ ಪದವಿರಾಸ್ತಿ
ಶಿಲ್ಪಪಡಿಗಳ ಸಂಖ್ಯೆ.....(Nil)
ಶಿಲ್ಪಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿರಾಗಿದೆ

24/8/15

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92